

大將作

聯合建築師事務所

TCT ARCHITECTURAL RESOURCES

台中市館前路19號11樓

11F-No. 19 KUAN CHEN ROAD, TAICHUNG

TEL:(04)23220083 FAX:(04)23223697

修正

REVISIONS

112.05.12

C版_不含4F~7F裝修

工程名稱

PROJECT

國際獸醫防疫人才培訓中心

暨獸醫教學醫院大樓

新建工程

建照圖

施工圖

變更圖

竣工圖

圖名

DRAWING TITLE

NO1.

電梯詳圖

簽章

SIGNATURE

比例 SCALE

日期 DATE

設計 DESIGN

1/200

112/5/12

林一川

繪圖 DRAWN

校核 CHK.

核准 APPR.

CHC

圖號 DRAWING NO.

版次 REV

A5-7

C版

T:\建築設計部\圖說及文件\A577中興大學獸醫教學醫院大樓\06—施工圖\112.05.12_施工圖說_第一次發包版 (不含4F~7F裝修)\D01—建築圖說\外參\圖樣_A577中興大學獸醫教學醫院大樓 .DWG

Plan view of the elevator shaft (1/40). The drawing shows the shaft layout with dimensions: 2300mm width, 3400mm height. It includes details for the door frame installation (門框安裝後加工面) and the fire door (全樓防火門) with a height of 2300mm. Various dimensions for the shaft walls, door frame, and fire door are provided.

升降路平面圖(1/40)

升降路四週牆壁內不得埋設
器具，導線管或水管。

Front view of the elevator shaft entrance opening (1/40). The drawing shows the opening dimensions: 1400mm width, 2200mm height. It includes details for the floor finish (地板加工面) and the opening dimensions (HH=2100). Various dimensions for the opening and floor are provided.

出入口留孔正面圖(1/40)

備註:若壁面為大理石時，大理石留孔
請以BOX尺寸放大5mm切割之。

Plan view of the elevator machine room (1/40). The drawing shows the machine room layout with dimensions: 2900mm width, 6500mm height. It includes details for the machine room equipment, such as the control panel (控制盤), and the machine room dimensions. Various dimensions for the machine room and equipment are provided.

機械室平面圖(1/40)

機械室內應有照明(100LUX)
及通風設備(40°C以下)

B-B view of the machine room. The drawing shows the machine room layout with dimensions: 400mm width, 300mm height. It includes details for the machine room equipment, such as the control panel (控制盤), and the machine room dimensions. Various dimensions for the machine room and equipment are provided.

B-B視圖

Cross-section view of the elevator shaft (1/200). The drawing shows the shaft layout with dimensions: 30200mm height, 5000mm width. It includes details for the shaft equipment, such as the control panel (控制盤), and the shaft dimensions. Various dimensions for the shaft and equipment are provided.

升降路斷面圖(1/200)

升降路正下方存在可進出之空間時，
配重側應設有安全機械裝置

升降機主要規格	
號機	NO 1
台數	1
型名	NEXIEZ-MR (參考規格)
用途	病床用
控制方式	VVVF
操作方式	2BC
載重量 (公斤) (人份)	1000 (15)
速度 (m/min.)	90
停止樓數	8 停
停止樓名	(B1,1-7F)
動力電源 (V) AC 3 ϕ 60Hz	380
照明電源 (V) AC 1 ϕ 60Hz	110
開門方式	2S(L)
附加設備	供行動不使用 火災回歸運轉裝置(FER) 刷卡感應控制

一. 注意事項:

- 1.電源電壓變動率應在+5%至-10%之變動範圍內。
- 2.為維持本升降機所定的性能及壽命，必須注意下列條件。
(1)月平均濕度在90%以下，日平均濕度95%以下。
(2)機械室及升降路內不得有灰塵或有害之化學氣體。
- 3.通往機械室之樓梯應便於通行，並應有扶手，樓梯之傾斜角度不得大於60度。
- 4.升降路四週牆壁內不得埋設器具，導線管或水管。
- 5.每樓出入口水平面之垂直樓高不得小於2600公厘。
- 6.使用廠牌：三菱、日立、東芝，或同等品。
- 7.電梯在保固期內維護其性能正常運轉及保養，為平時預防設備故障損壞，設備若有異常或故障，在保固期合約中，皆須立即修護，保固項目須包含維護保養。

二. 配合工程:

(1)建築工事:

- 1.升降路，機械室之建造工事及各樓出入口之鋼筋水泥踏樑築造工事。
- 2.機械室地板及各樓出入口(含乘場位置表示器、按鈕器等)之預留孔工事。
- 3.乘場門框或器具等安裝後其周圍壁面或地板之補平裝飾工事，本案電梯車廂地坪需採用2mm整件式乙烯基耐磨透心無縫地毯，詳A8-2-11。
- 4.機械室配管後之泡沫混凝土(10公分)鋪設及防塵工事。
- 5.機械室出入口設備及機器搬入後預留孔之回填工事。
- 6.機械室機器吊鉤之設置工事(至少3噸)。
- 7.機械室需具有防止雨水浸入之換氣設備(排風扇、百葉窗等)及照明設備工事。
- 8.坑底之防水、排水及機械室牆壁、地坪之水泥粉刷或防塵工事。
- 9.坑底下方若有使用時其建築結構必須符合強度之處理工事。
- 10.二台以上之坑底有段差時保護棚工事。
- 11.升降路以外之對講機用配管配線工事。
- 12.裝設消防緊急運轉或緊急回歸功能時,自升降路至火災信號接點間之配管配線工事。
- 13.鋼骨結構升降路時,導軌之支持樑、柱、鐵件，門框、主機支持樑及門框、信號器具支持鐵件。

(2)電源設備工事:

- 1.動力電源(含接地線)接至機械室總開關之電線，開關及開關箱等設備工事。
- 2.照明用電源接至機械室總開關之電線。開關及開關箱等設備工事。
- 3.電氣室電源設備規範.(每台)

號機	NO.1	
動力線mm ² (MAX.)	14(216M)	
照明線mm ² (MAX.)		
接地線mm ²	5.5	
變壓器(KVA)3相	10	
動力開關(A)3P	40	
照明開關(A)2P	30	

A5-7